DOOR SCHEDULE

(ALL ITEMS TO BE FURNISHED & INSTALLED BY CONTRACTOR, U.O.N.)

NO.	LOCATION	TYPE	SIZE W	SIZE H	SIZE T	MAT.	FRAME JAMB	FRAME HEAD	FRAME SILL	REMARKS		HARDWARE GROUP
01	ENTRY VESTIBULE TO EXTERIOR	–	9'–0" UNIT	7'–0" UNIT	–	–	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4 & 5	–
02	SALES TO ENTRY VESTIBULE	A	9'–0" UNIT	7'–0" UNIT	–	ALUM.	5/A6	8/A6	–	EXISTING TO REMAIN	(SEE NOTE 4 & 5	1
03	REGISTER AREA TO EXIT VESTIBULE	–	9'–0" UNIT	7'–0" UNIT	–	–	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4 & 5	–
04	EXIT VESTIBULE TO EXTERIOR	–	9'–0" UNIT	7'–0" UNIT	–	–	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4 & 5	–
05	NOT USED											
06	SALES TO EXTERIOR	–	3'–0"	7'–0"	–	HM	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4)	–
07	CPU TO PRESALES	–	3'–0"	7'–0"	–	HM	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4)	–
08	PRESALES TO EXTERIOR	D	4'–0"	7'–0"	1 3/4"	HM	10/A6	13/A6	11/A6	NEW DOOR	(SEE NOTE 4 & 6)	3
09	RECEIVING TO EXTERIOR	–	3'–0"	7'–0"		HM	–	–	–	EXISTING TO REMAIN	(SEE NOTE 4 & 6)	–
10	NOT USED											
11	NOT USED											
12	NOT USED											
13	KRU STOCK TO KRU OFFICE	F	3'–0"	7'–0"	1 3/4"	HM	9/A6	12/A6	–	NEW DOOR	(SEE NOTE 4)	2
14	NOT USED											
15	ELECTRICAL ROOM TO SALES	F	3'–0"	7'–0"	1 3/4"	HM	9/A6	12/A6	–	NEW DOOR	(SEE NOTE 6)	2
ID1	SALES TO PRE–SALES (IMPACT DOORS)	B	2'–3" PAIR	8'–0"	–	PLASTIC	6/A6	7/A6	14/A6	EXISTING DOOR NEW LOCATION	(OSI)	–
ID2	SALES TO PRE–SALES (IMPACT DOORS)	B	3'–3"	8'–0"	–	PLASTIC	6/A6	7/A6	14/A6	NEW DOOR	(OSI)	–

NOTES:

1) EXTERIOR FACE OF DOOR TO BE PAINTED TO MATCH EXISTING ADJACENT FINISH.
2) PAINT DOOR "TEAL"
3) PREPARE DOOR TO RECEIVE "DETEX" CYLINDER BOTH SIDES.
4) CONTRACTOR IS RESPONSIBLE TO INSURE EGRESS DOORS & "DETEX" DEVICE ARE OPERATIONAL TO COMPLY W/ LOCAL CODES. IF NOT, GC TO ADVISE "TRU" CPM FOR REPLACEMENT.
5) CONTRACTOR IS RESPONSIBLE TO INSURE AUTOMATIC SLIDING DOORS ARE OPERATIONAL FOR INTENDED USE, INCLUDING EGRESS. IF NOT, GC TO ADVISE "TRU" CPM FOR REPAIR.
6) PAINT EACH FACE OF NEW DOOR TO MATCH ADJACENT SURFACE.

DOOR ELEVATIONS



HARDWARE SCHEDULE

GROUP 1 – NOT USED

GROUP 2 TO HAVE (R ZONE DOOR & OFFICE DOORS)

1	1/2 PR. BUTTS STANLEY	FBB 179 4 1/2" x 4 1/2" 26D
1	LOCKSET BEST	93K7D15D–626 (LEVER HAND)
1	DR. CLOSER NORTON	7500 H–BF–AL
3	SILENCERS IVES	20
1	DR STOP IVES	407 B36D
1	KICKPLATE HAGER	10X34,16GA. 32D

GROUP 3 TO HAVE (SINGLE EXIT & CPU DOORS)

2	PR. BUTTS STANLEY	FBB 191 4 1/2 x 4 1/2 NRP 26D
1	DETEX ALARM (BATTERY)	ECL 8010 (CYLINDER KEYED)
1	THRESHOLD N.G.P.	425
1	SET WEATHERSTRIPPING N.G.P.	#135N FATT
2	PULL HAGER	9G 8"C. TO C., 32D (CPU DOOR ONLY)
1	DOOR SWEEP –N.G.P.	102AV
1	DOOR CLOSER NORTON	JL 7500BF–H
1	KICKPLATE HAGER	10" x 46", 16 GA. 32D (CPU DOOR ONLY)
1	BEST RIM CYLINDER	1E72 (CONSTRUCTION CORE, CPU DOOR ONLY)
1	WIND CHAIN (HEAVY DUTY)	

GROUP 4 TO HAVE (SINGLE EXIT DOORS)

2	PR. BUTTS STANLEY	FBB 191 4 1/2 x 4 1/2 NRP 26D
1	DETEX ALARM (BATTERY)	ECL 8010 (CYLINDER KEYED)
1	THRESHOLD N.G.P.	425
1	SET WEATHERSTRIPPING N.G.P.	#135N FATT
1	DOOR SWEEP –N.G.P.	102AV
1	DOOR CLOSER NORTON	JL 7500BF–H
1	WIND CHAIN (HEAVY DUTY)	

LEGEND

- NEW V.C.T TO MATCH EXISTING
- NEW CARPETING
- NEW GONDOLA CHANNEL OR PLATE
- EXISTING GONDOLA CHANNEL OR PLATE TO REMAIN
- EXISTING WALL OR PARTITION TO REMAIN
- NEW WALL OR PARTITION
- NEW DOOR
- EXISTING DOOR TO REMAIN

GENERAL NOTES

REFER TO SHEET A0 FOR LIST OF GENERAL NOTES.

KEYED NOTES

1. EXISTING SALES AREA FLOORING TO REMAIN. REPLACE ALL EXISTING VCT FLOORING WHERE DAMAGED IN SALES AREA, VESTIBULE, REGISTER AND SERVICE AREAS AT PRE CONSTRUCTION WALKTHROUGH. GC AND CPM FOR "TRU" TO DETERMINE QUANTITY OF VCT TO BE REPLACED.
2. WHERE THE NEW SALES AREA IS TO EXTEND INTO THE EXISTING PRE–SALES AREA, (SHADED AREAS) INSTALL NEW VCT FLOORING TO THE NEW SALES AREA LIMITS. APPLY FLOOR PATCHING MATERIAL AS REQUIRED TO PROVIDE A FLUSH TRANSITION FROM EXISTING TO NEW FLOOR TILE. GC TO PROVIDE VCT TO MATCH EXISTING.
3. NEW VCT FOR SALES EXTENSION AREAS AND PATCH WORK TO BE REVIEWED AND APPROVED BY TRU CPM PRIOR TO INSTALLATION.
4. PRE–SALES AREA FLOOR SURFACE TO REMAIN AS IS.
5. TRU VENDOR IS RESPONSIBLE FOR SUPPLYING AND INSTALLING THE ADHESIVE–BACKED VINYL RACETRACK DECAL AS SHOWN ON THE FLOOR PLAN. COORDINATE WITH FIXTURE PLAN AND TRU CPM.
6. EXISTING COLUMNS PREVIOUSLY IN PRE–SALES AREA, NOW IN EXPANDED SALES AREA, TO BE PAINTED SW1004 PURE WHITE TO DECK ABOVE. FURR OUT TO MATCH EXISTING COLUMNS IF APPLICABLE (FIELD VERIFY).
7. CONTRACTOR IS RESPONSIBLE FOR PAINTING WOOD ALIGNMENT PLATE (COLOR TO MATCH ADJACENT WALL OR STRUCTURE), AT ALL OPENINGS VISIBLE FROM SALES AREA AFTER FIXTURES HAVE BEEN INSTALLED.
8. CONTRACTOR IS RESPONSIBLE FOR PAINTING ALL UNPAINTED CEILINGS, WALLS, AND STRUCTURE IN THE PRE–SALES AND RECEIVING AREAS, TO MATCH EXISTING, ONLY IN AREAS VISIBLE FROM THE SALES FLOOR. COORDINATE WITH THE TRU CPM. G.C. TO PAINT WHITE ALL WALL GRAPHICS, DECALS, STRIPING, ETC. DO NOT PAINT SPRINKLER HEADS.
9. G.C. IS RESPONSIBLE FOR PAINTING INTERIOR WALLS @ CPU G.C. TO VERIFY IF EXTERIOR RAILINGS EXIST, & REPAIR/REPAINT AS NECESSARY.
10. VERIFY NUMBER OF LAYERS OF TILE IN EXIST. SALES AREA. G.C. TO INSTALL FILLER LAYER(S) AS REQUIRED TO BRING NEW TILE FLUSH w/EXISTING IN ALL EXPANDED SALES AREA'S.
11. JUVENILE REGISTRY. COORDINATE LOCATION OF UTILITIES W/ELECTRICAL DRAWINGS, AND LOCATION W/FIXTURE PLAN, (RF1) AND "TRU" CPM.
12. 6553 TOTAL SQ. FT. OF CARPET, FURN. BY TRU & INSTALLED BY CONTRACTOR. ADHESIVE AND REDUCER STRIP FURN. & INSTALLED BY CONTRACTOR (COLOR TO BE SELECTED BY TRU) EXACT DIMENSIONS TO BE GIVEN BY TRU CPM. (SEE FIXTURE PLAN)
13. CONTRACTOR TO REPLACE OR INSTALL NEW IMPACT DOORS AS SHOWN ON PLAN AND CONCEAL FRAME FROM TOP OF DOOR TO 12'–0" A.F.F. REFER TO DOOR SCHEDULE.
14. EXISTING DOOR AND FRAME PREVIOUSLY IN PRE–SALES AREA, PROPOSED TO BE IN SALES AREA, PAINT TO MATCH ADJACENT WALLS.
15. CONTRACTOR IS RESPONSIBLE FOR INFILLING BALANCE OF EXISTING MASONRY OR METAL STUD PARTITION ROUGH OPENINGS TO MATCH EXISTING ADJACENT SURFACE.
16. NEW DOOR AND FRAME. REFER TO DOOR SCHEDULE. PAINT TO MATCH APPROPRIATE COLOR SCHEME.
17. NEW PARTITION. PAINT TO MATCH ADJACENT WALL OR PARTITION.
18. BIKE ASSEMBLY COUNTER. COORDINATE LOCATION WITH FIXTURE PLAN (RF1), AND TRU CPM VERIFY UTILITY LOCATIONS WITH ELECTRICAL DRAWINGS.
19. NEW OR RELOCATED SECURITY SENSORS. COORDINATE LOCATION W/FIXTURE PLAN AND TRU CPM. PATCH VCT AS REQ'D AT ALL LOCATIONS.
20. EXISTING IMPACT DOOR ON NEW LOCATION.
21. NOT USED
22. STORAGE BIN. COORDINATE LOCATION W/RF1 FIXTURE PLAN AND "TRU" CPM.
23. CONTRACTOR TO FURNISH AND INSTALL 1 1/2" O.D. STEEL RAILING AT 36" A.F.F. COORDINATE LOCATION WITH TRU CPM.
24. CONTRACTOR TO REPAINT ALL SALES FLOOR COLUMNS SW1004 "PURE WHITE"
25. MANAGERS WORKSTATION. COORDINATE LOCATION OF UTILITIES W/ELECTRICAL DRAWINGS, AND LOCATION W/FIXTURE PLAN, (RF1) AND "TRU" CPM.
26. PAINT ALL THREADED RODS, UNISTRUT & CONDUIT TO MATCH EXISTING ADJACENT STRUCTURE.
27. NOT USED
28. EXISTING FIRE RISER AREA TO REMAIN. MAINTAIN ADEQUATE CLEARANCE AS REQUIRED BY LOCAL CODES.

    PROVIDE NEW RISER CLOSET AND ADEQUATE CLEARANCE AS REQUIRED AT EXISTING FIRE RISER.
29. FITTING ROOMS. COORDINATE LOCATION W/FIXTURE PLAN RF1 & OWNER'S REP.
30. G.C. TO PROVIDE & ATTACH PLASTIC LAMINATE END PANEL TO END OF FIXTURE AND WALL. COORDINATE LOCATION W/RF1
31. INFILL ALL FLOOR CRACKS, CONTROL JOINTS ETC. BEFORE APPLYING NEW FLOOR TILE.
32. WOOD ALIGNMENT PLATE @ ALL WALLS IN ROOM AS SHOWN. REFER TO DETAIL 2/A6
33. PROVIDE ANEMOSTAT GC5 SUPPLY DIFFUSER AND 8X6 DUCT WITH 1" INTERNAL LINER, TAP 75 CFM FROM EXISTING DUCT ABOVE RESTROOM.
34. NEW GYP. BD. CLG.. @ 9'–0" REFER TO 5/A6.
35. RGD. COORDINATE LOCATION OF UTILITIES W/ELECTRICAL DRAWINGS, AND LOCATION W/FIXTURE PLAN, (RF1) AND "TRU" CPM.



FLOOR PLAN

SCALE: 1/16" = 1'–0"

PLAN NORTH

Revisions

No	Date	Description
		PERMIT APPLICATION

Drawing References

No	Drawings

BID DATE: _____
CADD NAME: TR90CA01 PROJECT NO.: 4325
DRAWN BY: _____ CHECKED BY: _____
PROTOTYPE DESIGNATION: VERSION 2000–QTR–1 REV.1.00

ESTABLISHED 1896

LEHMAN ARCHITECTURAL GROUP, P.C.
39 WOODLAND ROAD . ROSELAND, NJ 07068
PHONE (973) 228 8800 . FAX (973) 228 9339

TOYS "R" US®

National Office
461 From Road
Paramus, NJ 07652
(201) 599–7800

This drawing is the Exclusive Property of TOYS "R" US. The information shown may not be used nor the Drawings Reproduced without permission of TOYS "R" US.

Location
PHILLIPSBURG
NEW JERSEY
1280 RT.22 & ST.JAMES AVE.

Drawing Title
FLOOR PLAN, DOOR SCHED. & DETAILS

Scale AS NOTED | Date 11–30–2000

Sheet No.
A1 0R